

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-26528-00-00
Spot: NWSWSENW Sec/Twnshp/Rge: 18-12S-18W
2040 feet from N Section Line, 1360 feet from W Section Line
Lease Name: GEORGE Well #: 1
County: ELLIS Total Vertical Depth: 3900 feet

Operator License No.: 4787
Op Name: TDL, INC.
Address: 1310 BISON RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	223		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/21/2013 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: DERBY Company: SOUTHWIND DRILLING, INC. Phone: (785) 259-1356

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE
Date/Time Plugging Completed: 06/21/2013 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st plug @1570 w/25 sx
2nd plug @855 w/100 sx
3rd plug @275 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP


KCC WICHITA

JUL 08 2013

RECEIVED

District: 04

Signed


(TECHNICIAN)

CM

JUN 24 2013