

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21634-00-00
Spot: SWSWNENE Sec/Twnshp/Rge: 33-8S-18W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: FINNESY Well #: 3
County: ROOKS Total Vertical Depth: 3450 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3449		150 SX
SURF	8.625	262		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2013 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 420 sx 60/40 pozmix 4% gel cement w/500 # hulls.
LKC and Arbuckle perforations squeezed off with 500 sx cement.
DV tool at 1316' w/375 sx cement.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2013 12:15 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3300' and pumped 160 sx cement w/350 # hulls.
Pulled tubing to 1850' and pumped 145 sx cement w/150 # hulls to circulate cement to surface.
Pulled all tubing. Topped off 5 1/2" casing w/20 sx cement.
Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.31876 -099.32919

Perfs:

Top	Bot	Thru	Comments
3397	3403		

Remarks: QUALITY OILWELL CEMENTING TICKET # 6912

Plugged through: TBG

KCC WICHITA

JUL 09 2013

RECEIVED

District: 04

Signed Pat Bedore
3/19/13 (TECHNICIAN)

CM

JUN 20 2013