

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05839-00-00  
Spot: SESWSE Sec/Twnshp/Rge: 22-11S-17W  
330 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: JOHANSEN Well #: 3  
County: ELLIS Total Vertical Depth: 3433 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3427		150 SX
SURF	10	1183		310 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2013 10:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: SMOKY HILLS WELL SERVICE Phone: (785) 885-8240

Proposed Plugging Method: Ordered 1175 sx 60/40 pozmix 4% gel cement, 7 bags cc, 1300 # hulls and 5 # fiber seal.  
PBTD - 2618'  
Junk in hole at 2611'.  
Perforations ARB - 3427' - 3433'  
GPS: 39.07536 -099.19141 Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/25/2013 4:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1100'.  
Smoky Hills ran in hole with tubing to 2604'. Allied rigged to tubing and pumped 75 sx cement w/3% cc and 200 # hulls. Left set 1 hour.  
Pulled tubing to 2108'. Allied mixed and pumped 200 sx cement w/300 # hulls.  
Pulled tubing to 1147'. Allied mixed and pumped 300 sx cement w/300 # hulls mixed in.  
Pulled tubing to 497'. Allied mixed and pumped 150 sx cement w/300 # hulls, 3% cc and one 5 # bag of fiber seal. Cement circulated to pit area.  
Pulled tubing. Shut in 7" casing and pumped 50 sx cement to circulate and pressure 10" casing and 7" casing with 200 psi and 200 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3427	3433		

Remarks: ALLIED CEMENTING CO TICKET # 56632

Plugged through: TBG

KCC WICHITA

JUL 08 2013

RECEIVED

District: 04

Signed [Signature]  
7/10/13 (TECHNICIAN)

CM

JUN 26 2013