

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20355-00-01  
Spot: E2SENWNW Sec/Twnshp/Rge: 22-10S-20W  
4290 feet from S Section Line, 4190 feet from E Section Line  
Lease Name: SAYLES Well #: 5  
County: ROOKS Total Vertical Depth: 3630 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3520		
CIBP		3580		
PROD 4.5		3629		150 SX
SURF 8.625		252		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2013 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 483-9169

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
LKC: 3174' - 3476'  
CIBP: 3520'

Plugging Proposal Received By: RICHARD WILLIAMS  
Date/Time Plugging Completed: 06/24/2013 12:15 PM

WitnessType: COMPLETE (100%)  
KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Ran tubing to 3400'. Allied pumped 125 sx cement w/250 # hulls. Pulled tubing to 1643'. Allied pumped 310 sx cement w/250 # hulls. Cement circulated. PTOH. Topped 4 1/2" casing off w/10 sx cement. Hooked up to backside and pumped 15 sx cement. Maximum pressure 200 psi. Shut in pressure 200 psi.

GPS: 39.17347 -099.5477

**Perfs:**

Top	Bot	Thru	Comments
3590	3595		
3562	3565		
3465	3476		
3433	3437		
3174	3182		

Remarks: ALLIED TICKET # 54137

Plugged through: TBG

**KCC WICHITA**  
**JUL 08 2013**  
**RECEIVED**

District: 04

Signed

*Richard Williams*  
7/19/13

(TECHNICIAN)

CM