

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-30030-00-00
Spot: NWSE Sec/Twnshp/Rge: 20-4S-18W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: STONEMAN Well #: 4
County: PHILLIPS Total Vertical Depth: 3455 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3325		150 SX
SURF	8	206		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2013 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PROD. Phone: (785) 302-1435

Proposed Plugging Method: Ordered 175 sx 60/40 pozmix 4% gel cement
Tubing cemented in hole.
Production perforations at 3105' - 3109'.
Perforated at 865' and 1430' (2 hole each)

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/21/2013 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 8 5/8" x 4 1/2" annulus and pumped 50 sx cement. Shut in pressure 100 psi.
Hooked to 4 1/2" x 2 3/8". Pressured up immediately to 1000 psi.
Hooked to 2 7/8" tubing. Pumped 120 sx cement. Maximum pressure 2000 psi. Shut in pressure 1800 psi.

GPS: 39.68887N -099.37264W

Perfs:

Top	Bot	Thru	Comments
3105	3109		

Remarks: ALLIED TICKET # 54706

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

JUL 05 2013