

TO: 15-131-20217-0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*ok to inv. as plug dt. falls w/in
5 yr. billing cutoff.*

API Well Number: 15-131-20217-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 18-1S-14E
500 feet from S Section Line, 1900 feet from E Section Line
Lease Name: MEYER Well #: 1-18
County: NEMAHA Total Vertical Depth: 4080 feet

Operator License No.: 31439
Op Name: KINNEY OIL COMPANY
Address: 1401 17TH ST STE 870
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	265		160 sx cement

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/08/2011 5:00 PM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN COX Company: SUMMIT DRILLING COMPANY Phone: (620) 344-1465

Proposed Plugging Method: 50' PLUG AT BOTTOM, 50' PLUG AT PRODUCING ZONES, 50' PLUG AT KC, CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 02/08/2011 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

HAD THE DRILL PIPE RAN TO 4040' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 3750' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 1460' AND PUMPED 15 SACKS OF CEMENT. PULLED THE PIPE UP TO 300' AND PUMPED 105 SACKS OF CEMENT TO THE SURFACE.

RECEIVED

JUL 03 2013

KCC Chanute Dist. #3

TH

Remarks:

Plugged through: DP

KCC WICHITA

JUL 05 2013

RECEIVED

District: 03

Signed Taylor C. Herman
7/18/13 (TECHNICIAN)