

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01527-00-00
Spot: SESWNE Sec/Twnshp/Rge: 14-9S-22W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: VAN LOENEN Well #: 6
County: GRAHAM Total Vertical Depth: 3806 feet

Operator License No.: 31434

String Size Depth (ft) Pulled (ft) Comments

Op Name: L & J OIL PROPERTIES, INC.

PROD 5.5 3803 150 SX

Address: 1700 N WATERFRONT PKWY BLDG 300,
WICHITA, KS 67206

SURF 8.625 247 150 SX

^ SEE T1 2, 3778

Handwritten signature and date: 7/15/13

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/03/2013 8:30 AM

Plug Co. License No.: 34266

Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC

Proposal Rcvd. from: JOEL STULL

Company: PRAIRIE HAWK WELL SERVICE L Phone: (785) 885-4272

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
No records of Alt II.
Production perforations: 3556' - 3572'

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/03/2013 12:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2400', 1750' and 1050'.
Ran tubing to 3260'. Allied pumped 100 sx cement w/250 # hulls. Pulled tubing to 2260'.
Allied pumped 120 sx w/250 # hulls. Pulled tubing to 1050' and pumped 95 sx cement.
Circulated cement. PTOH. Topped 5 1/2" casing off w/15 sx cement.
Hooked up to backside. Instant pressure at 500 psi.

Perfs:

Top	Bot	Thru	Comments
3568	3572		
3556	3559		

Remarks: ALLIED

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Richard Williams
7/18/13

(TECHNICIAN)

CM

JUL 08 2013