

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-22034-00-00  
Spot: SWSWNEW Sec/Twnshp/Rge: 36-16S-20W  
1185 feet from N Section Line, 1375 feet from W Section Line  
Lease Name: HOUSE Well #: 5-36  
County: RUSH Total Vertical Depth: 3893 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1077		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2013 9:00 AM  
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.  
Proposal Rcvd. from: JAY KRIER Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: 1ST PLUG AT 3855' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 50 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 07/14/2013 11:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

1ST PLUG AT 3855' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 50 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

KCC WICHITA

JUL 18 2013

RECEIVED

District: 01

Signed

Richard M. Lacey  
7/18/13 (TECHNICIAN)

RECEIVED

JUL 16 2013

KCC DODGE CITY