

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03442-00-00
Spot: NENENW Sec/Twnshp/Rge: 27-15S-13W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BER-SEL-ES Well #: 1-1
County: RUSSELL Total Vertical Depth: 3090 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3079		50 SX
SURF	8.625	226		100 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/20/2013 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 830' and 1450'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/20/2013 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3020' and pumped 150 sx cement w/250 # hulls.
Pulled tubing to 1500' and pumped 180 sx cement w/200 # hulls.
Cement circulated to pit.
POOH. Hooked up to casing and pumped 25 sx cement at 200 psi to shut in.
Hooked up to braden head and pumped 12 sx cement at 150 psi.

GPS: 38.72504 -098.75552

Perfs:

Top	Bot	Thru	Comments
3174	3252		
3079	3173		
3068	3072		
3061	3065		

Remarks: QUALITY CEMENTING TICKET # 6871

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
7/18/13 (TECHNICIAN)

CM

KCC WICHITA

JUL 08 2013

RECEIVED

JUN 21 2013