

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02201-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 28-10S-20W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: WILLIAMS B Well #: 2  
County: ROOKS Total Vertical Depth: 3761 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3755		150 SX
SURF	8.625	205		140 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2013 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 10 sx gel and 500 # hulls.  
Perforated at 2250', 1725', 825' and 200'.  
Squeezed-2828'- 2859' w/100 sx cement, 1092' - 1306' w/250 sx cement, 905' - 1300' w/200 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2013 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' and pumped 10 sx gel spacer followed by 50 sx cement w/100 # hulls.  
Pulled tubing to 2253' and pumped 125 sx cement w/200 # hulls.  
Pulled tubing to 994' and pumped 115 sx cement w/200 # hulls to circulate cement to surface.  
Hooked to 5 1/2" casing and pumped 50 sx cement to circulate 8 5/8" x 5 1/2" annulus and fill 5 1/2" casing.

GPS: 39.15704N -099.56443W

Perfs:

Top	Bot	Thru	Comments
3755	3761		
3659	3663		

Remarks: CONSOLIDATED TICKET # 37950

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Pat Bedore  
7/18/13 (TECHNICIAN)

CM

JUL 05 2013