

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01032-00-01
Spot: NENWNW Sec/Twnshp/Rge: 28-10S-20W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WILLIAMS OWWO Well #: 4
County: ROOKS Total Vertical Depth: 3840 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3837		150 SX
SURF	8.625	183		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2013 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: FRANCIS HITCHMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel spacer and 500 # hulls.
DV Tool at 1696' w/300 sx cement. Did not circulate.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2013 10:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3610' and pumped 12 sx gel spacer followed by 50 sx cement w/100 # hulls.
Pulled tubing to 2095' and pumped 225 sx cement to circulate to surface.
Pulled all tubing and topped off 5 1/2" casing with 35 sx cement.
Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 150 psi.
GPS: 39.16038N -099.56425

Perfs:

Top	Bot	Thru	Comments
3781	3785		
3774	3776		
3770	3772		
3674	3676		
3670	3672		

Remarks: CONSOLIDATED TICKET # 40043

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed _____

Pat Bedore
7/18/13 (TECHNICIAN)

(M)

JUL 05 2013