

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20273-00-01
Spot: NENESWNE Sec/Twnshp/Rge: 18-5S-20W
3815 feet from S Section Line, 1400 feet from E Section Line
Lease Name: WILTROUT Well #: 4
County: PHILLIPS Total Vertical Depth: 3800 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	300		300 SX
PROD	5.5	3486		400 SX
SURF	8.625	3732		600 SX

Well Type: SWD UIC Docket No: D19661.0 Date/Time to Plug: 06/26/2013 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 689-7567

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/1000 # hulls.
Hole in 5 1/2" casing from 797' - 820'
Drill bit stuck at 1643'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2013 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing in hole and screwed into stuck bit at 1643'. Pumped 245 sx cement w/75 # hulls.
Backed off tubing from bit. Pumped 75 sx cement w/300 # hulls.
Pulled tubing to 833' and pumped 110 sx cement w/375 # hulls to circulate cement to surface.
Pulled all tubing and topped off 5 1/2" casing w/20 sx cement.

GPS: 39.62146N -099.61404W

Perfs:

Top	Bot	Thru	Comments
3514	3696		

Remarks: SWIFT TICKET # 24831

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

7/18/13
* cc to MK 7/15/13

JUL 05 2013