

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-14166-00-01
Spot: E2SWNW Sec/Twnshp/Rge: 34-18S-15W
3300 feet from S Section Line, 4290 feet from E Section Line
Lease Name: YARMER Well #: 1
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 5364
Op Name: BEREN CORPORATION
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1900		100 SX
SURF	10.75	904		600 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/27/2013 8:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (785) 772-8649

Proposed
Plugging
Method:

Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2013 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 900'.
Ran tubing to 1800' and pumped 70 sx cement w/100 # hulls.
Pulled tubing to 900'. Circulated cement to surface w/75 sx cement w/50 # hulls.
Pulled tubing. Tied to casing. Circulated cement out surface pipe with 200 sx cement and 50 # hulls.

Perfs:

Top	Bot	Thru	Comments
1776	1786		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

Bruce Rodie
7/18/13 (TECHNICIAN)

CM

JUL 02 2013