

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24126-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 21-10S-18W
1490 feet from N Section Line, 1740 feet from W Section Line
Lease Name: PEAVEY Well #: 1
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 217 | | 170 sx |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/10/2013 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: MARK Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 07/10/2013 4:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st plug @1520 w/25 sx
2nd plug @917 w/100 sx
3rd plug @267 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed [Signature]
7/18/13 (TECHNICIAN) CM

JUL 10 2013

KCC WICHITA
Form CP-2/3

JUL 17 2013

RECEIVED