

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20297-00-00
Spot: NWSWSWNE Sec/Twnshp/Rge: 6-15S-12E
2260 feet from N Section Line, 2360 feet from E Section Line
Lease Name: WAUGH C Well #: 1
County: WABAUNSEE Total Vertical Depth: 3099 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	304		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2012 10:00 PM
Plug Co. License No.: 32854 Plug Co. Name: GULICK DRILLING, INC.
Proposal Rcvd. from: MIKE STAFFORD Company: GULICK DRILLING, INC. Phone: (620) 583-2978

Proposed Plugging Method: 50' PLUG AT BOTTOM, 50' PLUG AT PRODUCING ZONES, 50' PLUG AT KC, CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 10/14/2012 10:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Perfs:

HAD THE DRILL PIPE RAN TO 3060' AND PUMPED 35 SACKS OF CEMENT. PULLED THE DRILL PIPE UP TO 1250' AND PUMPED 15 SACKS OF CEMENT. PULLED THE DRILL PIPE UP TO 350' AND PUMPED 150 SACKS OF CEMENT TO THE SURFACE.

RECEIVED

JUL 03 2013

KCC Chanute Dist. #3

TH

KCC WICHITA

JUL 05 2013

RECEIVED

Remarks:

Plugged through: DP

District: 03

Signed

Taylor C. Herman
7/18/13

(TECHNICIAN)