

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21970-00-00
Spot: SESWSE Sec/Twnshp/Rge: 3-21S-6W
522 feet from S Section Line, 1692 feet from E Section Line
Lease Name: CONRAD EAST Well #: 1
County: RICE Total Vertical Depth: 3480 feet

Operator License No.: 33838
Op Name: GIVENS, BRET
Address: 1300 N GRAND
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3478	1728	100 SX
SURF	10.75	209		210 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2013 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-0895

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 06/26/2013 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3345' AND CAP WITH 7 SX'S CEMENT. CUT CASING OFF AT 1728', AND PULL TO 950' AND PUMP 50 SX'S CEMENT. PULL CASING TO 550' AND PUMP 50 SX'S CEMENT. PULL CASING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF. USED APPROX. 275 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3395	3415	CSG	

KCC WICHITA
JUL 09 2013
RECEIVED

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-38597. DENIED TA WELL -- HFLD.

Plugged through: CSG

District: 02

Signed

Virgil Clothier
7/18/13
(TECHNICIAN)