

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20178-00-00
Spot: S2SWNWNW Sec/Twnshp/Rge: 18-5S-21W
1020 feet from N Section Line, 330 feet from W Section Line
Lease Name: NOONE Well #: 6
County: NORTON Total Vertical Depth: 3536 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3534		150 SX
SURF	8.62	205		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/27/2013 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO Phone: (785) 259-1928

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforated at 1725' and 1050'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/27/2013 3:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Tubing at 3464'. Pumped 75 sx cement w/100 # hulls.
Pulled tubing to 2331' and pumped 75 sx cement w/100 # hulls.
Pulled tubing to 1198' and pumped 90 sx cement to circulate cement to surface.
Pulled all tubing, hooked to 4 1/2" casing and pumped 35 sx cement. Shut in pressure 700 psi.
Hooked to 8 5/8" x 4 1/2" annulus and pumped 25 sx cement. Shut in pressure 200 psi.

GPS: 39.62264N -099.73940W

Perfs:

Top	Bot	Thru	Comments
1725	1725		
1050	1050		

Remarks: ALLIED CEMENTING TICKET # 60806

Plugged through: TBG

KCC WICHITA

JUL 15 2013

RECEIVED

District: 04

Signed

7/18/13

Pat Bedore
(TECHNICIAN)

CM

JUL 05 2013