

State of Kansas



15-105-20118-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

02-19-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Damme of Red Tiger Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Frontier Oil Company

Complete Address: 1720 Wichita Plaza Wichita, Ks.

Lease Name: Urban "H" Well No. 1

Location: SW SW NE Sec. 16 Twp. 16 Rge. 17 (E)(W) X

County Rush Total Depth 3293 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Damme was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 400' and displace

25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, and 2

sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cem.

Very truly yours,

[Signature]
Conservation Division Agent