



15-145-20199-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1968
CONSERVATION DIVISION
Wichita, Kansas
11-20-1968

Dear Sir:

Mr. Burris of Chief Drlg Co., Inc. has this

date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg Co., Inc.

Complete Address: Box 797 Great Bend, Kansas

Lease Name: Baggall Well No. 1

Location: CW/2 NW SE Sec. 16 Twp. 16 Rge. 17 (E)(W) X

County: Rush Total Depth 3570' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Burris was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
20 sc cement thru drill pipe. Heavy mud to 510' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Massey
Conservation Division Agent