

State of Kansas



15-135-20284-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

09-25-1969
RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. McFarland of Solar Oil Co. has this
date requested permission to plug the following described well:

Mr. McFarland guarantees payment of the plugging fee.

Operator's full Name: Solar Oil Co.

Complete Address: 1117 Union Nat'l Bldg., Wichita, Ks.

Lease Name: Adolph Well No. 1

Location: SW SW NW Sec. 13 Twp. 20 Rge. (E)(W) 26

County: Ness Total Depth 4530 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. McFarland was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 700' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. Z. Messing
Conservation Division Agent