

State of Kansas



15-135-21530-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
11-13-1978
NOV 15 1978

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. French of Pickrell Drlg. has this

date requested permission to plug the following described well:

Mr. French guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 205 Litwin Bldg., Wichita, Ks.

Lease Name: Betz "I" Well No. 2

Location: 150° NW of C SE SE Sec. 1 Twp. 20 Rge. (E)(W) 26

County: Ness Total Depth 4570° Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. French was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 900° thru drill
pipe. Heavy mud to 240° set 25 sk cmt plug thru drill pipe. Heavy
mud to 40° set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Messery
Conservation Division Agent