

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
DEC 19 1966
12-19-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Reddick of Bowers Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Reddick guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Axline "B" Well No. # 1

Location: C SE NW Sec. 8 Twp. 31 Rge. 11 (E)(W)W

County Barber Total Depth 4472' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Reddick was instructed to plug the well as follows:

290' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 290', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving
Conservation Division Agent