



15-165-20676-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1978  
02-06-1978  
CONSERVATION DIVISION  
WICHITA, KANSAS

Dear Sir:

Mr. Norwood of DNB Drlg. has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Thomas E. Black d/b/a Black Petro. Co.

Complete Address: 545 O. W. Garvey Bldg., Wichita, Ks.

Lease Name: Urban Well No. 1

Location: SE SW NE Sec. 24 Twp. 16 Rge. (E)(W) 17

County: Rush Total Depth 3335 Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 420' thru drill pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Lee M. [Signature]  
Conservation Division Agent