

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22379-00-00  
Spot: SWSWSENE Sec/Twnshp/Rge: 25-20S-29W  
2500 feet from N Section Line, 1200 feet from E Section Line  
Lease Name: CHURCH & SHAFFER Well #: 1  
County: LANE Total Vertical Depth: 4792 feet

Operator License No.: 6569  
Op Name: CARMEN SCHMITT, INC.  
Address: PO BOX 47  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2122		CEMENTED WITH 185 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	4.5	4794	0	WITH 225 SX CMT
SURF	8.625	222		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/03/2013 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT Phone: (620) 793-2540

Proposed Plugging Method: SQUEEZE PERFS WITH 50 SX CMT & 250# HULLS. PUMP DOWN CASING WITH 25 SX GEL & 140 SX CMT. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/03/2013 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 50 SX CMT WITH 100# HULLS & 50 7/8" RUBBER BALL SEALERS ON BOTTOM. PUMP GEL SPACER BACK TO 2500'. PUMP 175 SX CMT FROM 2500' TO 0'. AFTER 1 HOUR, CMT IN 4 1/2" CASING IS 15' FROM SURFACE. TOP OFF WITH QUICKCRETE. PUMP 4 SX CMT DOWN THE ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
4550	4552		
4525	4529		
4474	4478		
4400	4404		
4370	4374		
4320	4325		
4264	4452		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

KCC WICHITA  
JUL 22 2013  
RECEIVED

District: 01

RECEIVED

JUL 19 2013

KCC DODGE CITY

Signed

  
(TECHNICIAN)