

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20253-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 31-25S-29W
4612 feet from S Section Line, 4576 feet from E Section Line
Lease Name: RENICK BROTHERS Well #: 2-31
County: GRAY Total Vertical Depth: 5030 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1850		CEMENTED TO SURFACE
PROD	5.5	5028	0	WITH 150 SX CMT
SURF	8.625	387		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2013 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 150# HULLS ON BOTTOM. PLUG AT 1900' WITH 30 SX CMT. FILL WITH CMT FROM 975' TO 0'. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2013 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX CMT & 150# HULLS AT 4830'. 1ST PLUG AT 3500' WITH 30 SX CMT W/100# HULLS. 2ND PLUG AT 1900' WITH 30 SX CMT. 3RD PLUG AT 975' TO 0' WITH 90 SX CMT. TOOH W/TBG. TOP OFF CASING WITH 10 SX CMT. PUMP 15 SX CMT DOWN ANNULUS TO 500#.

Perfs:

Top	Bot	Thru	Comments
4898	4906		

KCC WICHITA
JUL 22 2013
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED 10 YR TA** USED COMMON CEMENT BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED

JUL 19 2013

KCC DODGE CITY