

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-21082-00-01  
Spot: SWSWNW Sec/Twnshp/Rge: 34-29S-34W  
2989 feet from S Section Line, 4969 feet from E Section Line  
Lease Name: MURPHY Well #: D-3  
County: HASKELL Total Vertical Depth: 5700 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6200 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1900		WITH 2 SX CMT
CIBP		5200		WITH 2 SX CMT
CIBP		5374		WITH 2 SX CMT
PC		2975		WITH 60 SX CMT
PROD	5.5	5577	1847	WITH 170 SX CMT
SURF	8.625	1828		WITH 465 SX CMT

Well Type: EOR UIC Docket No: E28039.6 Date/Time to Plug: 07/18/2013 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: CIBP @ 5400' WITH 2 SX CMT. CIBP @ 5200' WITH 2 SX CMT. CIBP @ 1900'. LOAD CASING WITH GEL & SHOOT OFF CASING. PLUG AT 1850' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 07/18/2013 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 5374' WITH 2 SX CMT, 5200' WITH 2 SX CMT, 1900' WITH 2 SX CMT.  
FILL WITH MUD. 1ST PLUG AT 1840' WITH 50 SX CMT. 2ND PLUG AT 731' WITH 50  
SX CMT. 3RD PLUG AT 30' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5455	5480		
5430	5478		
5428	5454		
5270	5358		

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

JUL 22 2013

RECEIVED

District: 01

RECEIVED

JUL 19 2013

KCC DODGE CITY

Signed

*Ken Jehlik*  
(TECHNICIAN)  
cc to KCC 7/23/13

*ADK*