

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03417-00-01  
Spot: N2N2SW Sec/Twnshp/Rge: 32-8S-19W  
2310 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: ROSTOCIL Well #: 1  
County: ROOKS Total Vertical Depth: 3307 feet

Operator License No.: 31171  
Op Name: CONTINENTAL OPERATING CO.  
Address: 1221 MCKINNEY STE 3700  
HOUSTON, TX 77010

*3509 PER  
RBRING/TD/  
STRINGS*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING CO. Phone: \_\_\_\_\_

*[Signature]*  
7/26/13

Proposed  
Plugging  
Method:

Got to bottom and twisted off drill pipe and 3 collars. Left 37 jts. tubing and 3 drill collars in hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/21/2013 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

06/14 Ran tubing to 2000' and pumped 400 sx 60/40 4% gel cement. Didn't circulate. Pumped 500 more sx cement w/500# hulls. Didn't circulate.  
06/17 Tagged cmt @1200'.  
06/17 Ran tubing to 1200' and pumped 350 sx cmt w/500# hulls. Didn't circulate.  
06/21 Tagged cmt @ 750'. Pumped 145 sx cmt w/400# hulls. Cement circulated.

Remarks:

Plugged through: TBG

KCC WICHITA  
JUL 23 2013  
RECEIVED

District: 04

Signed

*[Signature]*  
7/25/13  
(TECHNICIAN)

CM