

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-00155-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 5-32S-9W
330 feet from N Section Line, 2310 feet from E Section Line
Lease Name: BERRY Well #: 2
County: HARPER Total Vertical Depth: 4440 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>31191</u>	PROD	4.5	4436		120 SX
Op Name: <u>R & B OIL & GAS, INC. 912 N. LOSAN</u>	SURF	8.625	210		140 SX
Address: <u>124 N MAIN - PO BOX 195</u> <u>ATTICA, KS 67009</u>	(Address of 6/2013) (Current)				

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/12/2013 8:00 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Revd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE Phone: _____

[Handwritten signature]
7/26/13

Proposed Plugging Method: SET CIBP 50' ABOVE TOP PERFS & CAPP WITH 2 SKS CEMENT. 35 SX 1400', 35 SX 900'. CIRC CEMENT FROM 260'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 07/12/2013 11:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP AT 4298' & CAPPED WITH 2 SXS CEMENT. NO PIPE RECOVERY. SHOT 4 HOLES AT 1400' & PUMPED 35 SX CEMENT. SHOT 4 HOLES AT 900' & PUMPED 35 SX CEMENT. SHOT 4 HOLES AT 260' & CIRCULATED CEMENT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4362	4377	CSG	

KCC WICHITA
JUL 19 2013
RECEIVED

Remarks: ALLIED CEMENT. COMMON 3% CACL.

Plugged through: CSG

District: 02

Signed [Signature]
7/26/13 (TECHNICIAN)