

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20446-00-00
Spot: W2NE Sec/Twnshp/Rge: 36-32S-11W
3712 feet from S Section Line, 2285 feet from E Section Line
Lease Name: COLEMAN Well #: 1
County: BARBER Total Vertical Depth: 4500 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN, PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3895		WITH 5 SX CMT
PROD	5.5	4499	2600	WITH 125 SX CMT
SURE	8.625	249		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/26/2013 8:30 AM
Plug Co. License No.: 30346 Plug Co. Name: SHAWNEE WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CAPPS Company: SHAWNEE WELL SERVICE, INC. Phone: (620) 254-7893

Proposed Plugging Method: SET CIBP @ 4895' WITH 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2013 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3895' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
(UNABLE TO GET CIBP ANY DEEPER DUE TO ROUGH CASING) 1ST PLUG AT 612'
WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 292' WITH 50 SX CMT. 3RD PLUG AT
40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4450	4460		
445	4460		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

KCC WICHITA

JUL 18 2013

RECEIVED

District: 01

Signed Stephen J. Pfeifer
7/26/13 (TECHNICIAN)

RECEIVED

JUL - 1 2013

KCC DODGE CITY