

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23637-00-00  
Spot: N2S2NW Sec/Twnshp/Rge: 4-18S-14W  
3630 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: FRIEB Well #: 9  
County: BARTON Total Vertical Depth: 3630 feet

Operator License No.: 4323  
Op Name: REICHLINGER, GARY DBA REICHLING  
Address: 118 W 8TH ST PO BOX 4  
YORK, NE 68467

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP   |       | 3490       |             |          |
| PROD   | 5.5   | 3612       |             | 250 SX   |
| SURF   | 8.625 | 207        |             | 175 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/08/2013 9:30 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: GARY REICHLINGER Company: REICHLINGER BUS. Phone: (402) 362-4191

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls and 13 sx gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/08/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations at 1500'.  
Ran tubing to 3400' and pumped 13 sx gel followed with 50 sx cement.  
Pulled tubing to 1500' and pumped 80 sx cement.  
Pulled tubing to 750' and pumped 100 sx cement. Circulated cement to surface on casing.  
Well has a DV tool at 970'. Backside is full.

GPS: 38.51640 -09888101

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3459 | 3465 |      |          |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: ESGT &

KCC WICHITA  
JUL 23 2013  
RECEIVED

District: 04

Signed Bruce Rodie  
7/26/13 (TECHNICIAN)

CM

JUL 15 2013