

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23145-00-01
Spot: SESWNWSE Sec/Twnshp/Rge: 22-6S-20W
1600 feet from S Section Line, 2260 feet from E Section Line
Lease Name: CHAPMAN Well #: 5-X
County: ROOKS Total Vertical Depth: 3730 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PKR | | 3350 | | |
| PROD | 4.5 | 3727 | | 150 SX |
| SURF | 8.625 | 236 | | 175 SX |
| T1 | 2.375 | 3618 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2013 12:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION INC. Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing leaks from 1450' - 1900'.
PC at 1746.3' w/352 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/10/2013 4:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3670' and pumped 100 sx cement w/200 # hulls.
Pulled tubing to 2200' and pumped 50 sx cement w/200 # hulls. Bridged off 200 psi.
Pulled tubing to 1500' and pumped 100 sx cement to circulate cement to surface.
Pulled all tubing and topped off 4 1/2" casing w/15 sx cement.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured to 1000 psi immediately.

GPS: 39.51449N -099.53584W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3656 | 3659 | | |
| 3651 | 3653 | | |
| 3597 | 3598 | | |
| 3578 | 3582 | | |
| 3562 | 3566 | | |

Remarks: ALLIED CEMENTING TICKET # 54148

Plugged through: TBG

KCC WICHITA
JUL 23 2013
RECEIVED

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

JUL 15 2013