

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-35742-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 31-21S-8W
4936 feet from S Section Line, 4686 feet from E Section Line
Lease Name: SMITH E Well #: 1
County: RICE Total Vertical Depth: 3790 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3300		
PROD	4.5	3420		75 SX
SURF	8.625	190		75 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/15/2013 1:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Revd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE'S Phone: (620) 960-1288

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: PATRICK SHIELDS
Date/Time Plugging Completed: 07/15/2013 5:25 PM

WitnessType: PARTIAL
KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 3300' AND CAP WITH 2 SX'S CEMENT.
PERFORATE AT 1200', 750', AND 250'. RUN TUBING TO 1200' AND PUMP 35 SX'S
CEMENT WITH 1.5% CC AND 100 LBS COTTON HULLS. LET SET FOR 1 HOUR AND
TAGGED AT 1050'. PULL TUBING TO 750' AND PUMP 35 SX'S CEMENT WITH 1.5%
CC AND 100 LBS'S COTTON HULLS. PULL TUBING TO 250' AND CIRCULATE
CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. USED 190 SX'S TOTAL
CEMENT.

Perfs:

Top	Bot	Thru	Comments
3358	3380	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #42045.

Plugged through: TBG

KCC WICHITA

JUL 19 2013

RECEIVED

District: 02

Signed

Virgil Clothier
7/24/13
(TECHNICIAN)

✓ SK