

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20177-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 34-9S-33W
1235 feet from S Section Line, 3928 feet from E Section Line
Lease Name: WIENS Well #: 3
County: THOMAS Total Vertical Depth: 4690 feet

Operator License No.: 4967
Op Name: BERENERGY CORPORATION
Address: PO BOX 5850
DENVER, CO 80217

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2241		
PROD	5.5	2685		500 SX
SURF	8.625	376		360 SX
T1	2.375	2241		

Well Type: SWD UIC Docket No: D19553.0 Date/Time to Plug: 06/01/2013 1:00 PM
Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC
Proposal Rcvd. from: DAN HALL Company: BERENERGY CORP Phone: (303) 969-9610

Proposed Plugging Method: 8 5/8" surface casing set at 376' w/360 sx cement. 5 1/2" production casing set at 2685' w/500 sx cement. TD 4690', PBDT 2549'. Perforations: 2435' - 2485'.
Ordered 320 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2013 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 2400' and pumped 150 sx cement w/500 # hulls.
Pulled tubing to 1650' and pumped 140 sx cement. Cement to surface.
Pulled tubing to surface. Topped with 10 sx cement. Ran out of cement. 5 1/2" casing to be topped off on July 2 2013.
July 2 2013 - Pumped 20 sx cement. 5 1/2" casing full.
Cement visible in 8 5/8" surface casing.
GPS: 39.22350N -100.99489W

Perfs:

Top	Bot	Thru	Comments
2435	2485		

Remarks: ALLIED CEMENT TICKET # 60.337

Plugged through: TBG

KCC WICHITA
JUL 23 2013
RECEIVED

District: 04

Signed Darrel Dipman
7/24/13 (TECHNICIAN)

cc to UIC 7/23/13

CM

JUL 05 2013