

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-23788-00-00
Spot: NENENENW Sec/Twnshp/Rge: 15-24S-17E
5115 feet from S Section Line, 2690 feet from E Section Line
Lease Name: RILEY Well #: 3
County: WOODSON Total Vertical Depth: 1407 feet

Operator License No.: 31436

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.375	1190		96 SX
SURF	7	50		12 SX

Op Name: SPECHT, ARCHIE E. DBA SPECHT FARMS

Address: 2404 160TH RD
PIQUA, KS 66761

Handwritten signature

Well Type: EOR

UIC Docket No: E19280.2

Date/Time to Plug: 12/07/2012 12:00 AM

Plug Co. License No.: 31436

Plug Co. Name: SPECHT, ARCHIE E. DBA SPECHT FARMS

Proposal Rcvd. from: BRIAN SPECHT

Company:

Phone: (620) 363-1834

Proposed Plugging Method: ONE INCH FILL-UP FROM TD TO SURFACE WITH CEMENT SLURRY.

Plugging Proposal Received By: STEVE KORF

Witness Type: NONE

Date/Time Plugging Completed: 12/10/2012 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.375" casing that was cemented inside the 7" surface casing to TD. Pumped 6 sacks of cement through the 1" pipe inside the 2.375" casing at TD. Pulled 1" pipe to 1227'. Pumped 6 sacks of cement through the 1" pipe inside the 2.375" casing at 1227'. Pulled 1" pipe to 1017'. Pumped 6 sacks of cement through the 1" pipe inside the 2.375" casing at 1017'. Pulled 1" pipe to 807'. Pumped 6 sacks of cement through the 1" pipe inside the 2.375" casing at 807'. Pulled 1" pipe to 597'. Pumped 6 more sacks of cement through the 1" pipe inside the 2.375" casing till cement reached surface. Pulled the rest of the 1" pipe. Returned later and ran 1" pipe inside the 2.375" to 180' and tagged cement. Circulated 3 sacks of cement through the 1" pipe to surface. Pulled 1" pipe and topped well off with cement. A total of 33 sacks of portland cement was reported used to plug this well.

RECEIVED

JUL 16 2013

KCC Chanute Dist #3

RD

KCC WICHITA

JUL 19 2013

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed

Handwritten signature
cc to MC 7/24/13
7/26/13

(TECHNICIAN)