

1052418

TO: STATE CORPORATION COMMISSION

API NUMBER 15-165-19003-00-00  
C NE SW SEC. 29, T 16 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LIPPERT "B" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY RUSH 115.08

OPERATOR LICENSE # 32278 8/16

WELL TOTAL DEPTH 3541 FEET

OPERATOR: TENGASCO, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 3522' WITH 275 SX

NAME AND PO BOX 458

SURFACE CASING: SIZE 8 5/8" @ 205' WITH 135 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31 RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 16 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM AVEN WEAVERLING

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: DV @ 1130' WITH 550 SX CEMENT.

RAN TUBING TO 2081' & HIT BRIDGE. PULLED TUBING UP TO 2050' & PUMPED 55 SX CEMENT WITH

2 SX HULLS. PULLED TUBING TO 805' & CIRCULATED CEMENT TO SURFACE WITH 55 SX CEMENT.

PULLED TUBING & TOPPED OFF 4 1/2" WITH 5 SX CEMENT. PUMPED 15 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULUS

MAXIMUM PRESSURE 500#. SHUT IN 500#. PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 16 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

RAN TUBING TO 2081' & HIT BRIDGE. PULLED TUBING UP TO 2050' & PUMPED 55 SX CEMENT WITH

2 SX HULLS. PULLED TUBING TO 805' AND CIRCULATED CEMENT TO SURFACE WITH 55 SX CEMENT.

PULLED TUBING & TOPPED OFF 4 1/2" WITH 5 SX CEMENT. PUMPED 15 SX CEMENT DOWN 8 5/8" X 4 1/2" ANNULUS

MAXIMUM PRESSURE 500 PSI. SHUT IN PRESSURE 500 PSI.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

RECEIVED  
STATE CORPORATION COMMISSION  
08-22-2000  
AUG 22 2000

I (DID) OBSERVE THIS PLUGGING

INVOICED

SIGNED Richard W. Lacey  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

DATE 8/28/00

FORM CP-2/3

INV. NO. 2001060543