

1060207

15-165-26295-0000

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED 02/21/70
C SW SEC. 29, T 16 S, R 17 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LIPPERT "B" WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY RUSH 114, 99

OPERATOR LICENSE # 32278 6/20

WELL TOTAL DEPTH 3538 FEET

OPERATOR: TENGASCO, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 3537' WITH 275 SX

NAME AND PO BOX 458

SURFACE CASING: SIZE 8 5/8" @ 209' WITH 135 SX

ADDRESS HAYS, KS 67601

RECEIVED
ST. CORPORATION COMMISSION

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

JUL 6 2000
07-06-2000

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER

Conservation Division
Wichita, Kansas

ADDRESS PO BOX 31 RUSSELL, KS 67665

COMPANY TO PLUG AT: HOUR: 10:05 AM DAY: 20 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM BILL LEIKAM

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 3309-27. CIBP @ 3332'. DV TOOL AT 1110' WITH 500 SX TO SURFACE.

SPOT 25 SX CEMENT AND 150# HULLS AT 3200'. GEL SPACER TO 1100' THEN 60 SX CEMENT TO

SURFACE. PULLED TUBING AND TOPPED OFF WITH 15 SX CEMENT. TIED ONTO BACKSIDE PUMPED 10 SX

PRESSURED TO 500# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 20 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

SPOT 25 SX CEMENT AND 150# HULLS AT 3200'. GEL SPACER TO 1100' THEN 60 SX CEMENT TO

SURFACE. PULLED TUBING AND TOPPED OFF WITH 15 SX CEMENT. TIED ONTO BACKSIDE PUMPED 10 SX

PRESSURED TO 500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 7/10/00 SIGNED

Michael Maier (TECHNICIAN)

Handwritten initials and signature

FILE NO. 1060036

FORM CP-2/3