

15-165-20064-00-00

To: 1 120996  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-14

API NUMBER 15- Drilled 10/18/67

C SW, SEC. 26, T 16 S, R 17 W/E  
1320 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3456

Lease Name Roth B Well # 1

Operator: AFG Energy Inc.  
Name & Address P.O. Box 458  
Hays, KS 67601-0458

County Rush 117.65

Well Total Depth 3620 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor AFG Energy License Number 3456

Address P.O. Box 458, Hays, KS 67601-0458

Company to plug at: Hour: 10 a.m. Day: 14 Month: 12 Year: 19 94

Plugging proposal received from Terry Piesker

(company name) AFG Energy (phone) 913-625-6374

were: 4 1/2" at 3152' w/150 sx cement, PBTB 3114', Perfs at 3055-61', DV @ 1170' w/500 sx cement

1st plug pump 300 lbs. hulls and 65/35 Pozmix 8% gel to fill.

Check annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 14 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 300 lbs. hulls and 150 sx

cement. Pumping pressure 0-500 psi and shut in 200 psi.

2nd plug pumped into 8 5/8" X 4 1/2" annulus with 5 sx cement. Shut in pressure 600 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 21 1994  
12-21-1994  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

observe this plugging.

Signed W. J. Rankin  
(TECHNICIAN)

INVOICED  
DATE 1-3-9  
INV. NO. 41933