

To: 1 070413  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

APR 7 1987  
API NUMBER 15- 165-21,356 -00-00 <sup>32</sup>  
SW NW NW, SEC. 26, T 16 S, R 17 W/E  
4290 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4668

Lease Name Urban Well # D-2

Operator: Seville Drilling Corporation  
Name & Address P.O. Box 668  
La Crosse, KS 67548

County Rush 122.85  
Well Total Depth 3780 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1182

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Seville Drilling Corporation License Number 4668

Address P.O. Box 668, La Crosse, KS 67548

Company to plug at: Hour: 3 p.m. Day: 7 Month: 4 Year: 19 87

Plugging proposal received from Daniel Stegman

(company name) Seville Drilling Corporation (phone) 913-222-2633

were: 5 1/2" at 3780' PBD 3390' Perfs at 3051-3372' Elevation 2037' GL  
1st plug squeeze perfs with 100 sx cement, 2nd plug at 1200' with 20 sx cement,  
3rd plug at 600' with 20 sx cement, 4th plug at 40' with 5 sx cement,  
5th plug squeeze 8 5/8" X 5 1/2" with 100 sx ATL.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:35 p.m. Day: 7 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set packer at 2500', squeezed 100 sx of cement,  
2nd plug pumped gel from 2500-1200', 20 sx cement at 1200',  
3rd plug pulled tubing to 1040' and pumped gel to 600', spotted 20 sx cement at 600',  
4th plug pulled tubing to 440' and pumped gel to 40', cement from 40-0' with 10 sx. cement,  
Used 60/40 Pozmix 2% gel, 3% cc for above plugs. Pumped 100 sx ATL down 8 5/8" annulus-5th plug  
Maximum pressure 1200 psi and shut in 400 psi (8 5/8").

Remarks: No recovery. Used 60/40 Pozmix 2% gel, 3% cc by Allied; also ATL by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-15-87

INV. NO. 16543

RECEIVED  
APR 13 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Dan Gordon  
(TECHNICIAN)

4-7 MAY 14 1987

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84