

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-20982-00-00

NE/4, Sec. 25, T 16 S, R 17 W/E

(SWSWNE) feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from W/E section line

Operator License # 5140

Lease Name SHERWOOD "A" Well # 1

Operator: FRONTIER OIL COMPANY  
Name & Address 1720 KS ST. BANK Bldg.  
WICHITA, KS 67202

County RUSH

Well Total Depth 3575 feet

Conductor Pipe: Size 8 7/8 feet 251'

Surface Casing: Size 4 1/2 feet 3574'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ROCKHOLD ENGINEERING INC License Number 5111

Address BOX 698, GREAT BEND, KS 67530

Company to plug at: Hour: 11:30 AM Day: 11 Month: Nov. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO DEACON Pulley

(company name) Rockhold (phone) \_\_\_\_\_

were: Use 50/50 Poz mix, 4% gel - 3% CC. - Sanded bottom to 2950 and put on 4 sy Cmt. Recovered 2100' of 4 1/2". Pumped 4 sy hulls, 15 sy gel, 50 sy Cmt, 10 sy gel, 7 sy hulls and released 8 7/8 plug followed by 100 sy. Cmt.

Orders by P. Luthi Signed R. B. Arbuttan (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45 pm Day: 11 Month: Nov Year: 1982

ACTUAL PLUGGING REPORT Plugged as ordered.  
Cementing by Allied.

Remarks: Perfs @ 2994' to 3002'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1982  
CONSERVATION DIVISION  
Wichita, Kansas  
11-15-1982

I hereby certify that the above plugging instructions were given as herein stated and that I ~~did~~ <sup>did</sup> observe this plugging.

Signed R. B. Arbuttan (TECHNICIAN)

INVOICED

DATE 11-23-82

NO. 1679-W