

1030188

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-21,216-00-00  
NW NW NW, SEC. 24, T 16 S, R 17 W  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5900  
Operator: Lawbanco Drilling, Inc.  
Name & Address: Box 289  
Natoma, KS 67651

Lease Name Urban Well # 1  
County Rush  
Well Total Depth 3545 115.21 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pioneer Drilling License Number 5665

Address 308 West Mill, Plainville, KS 67663

Company to plug at: Hour: 2:00 pm Day: 28 Month: May Year: 19 84

Plugging proposal received from Tom Alm

(company name) Lawbanco (phone) 913-885-4676

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1140' with 50 sx cement

2nd plug at 760' with 50 sx cement

3rd plug at 240' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement.

Plugging Proposal Received by Steve Shumant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 pm Day: 28 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1140' with 50 sx cement, 2nd plug at 760' with 50 sx cement, 3rd plug at 240' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 6-6-84

INV. NO. 1899  
5-28

JUN 18 1984

Signed Steve Shumant  
(TECHNICIAN)