

1 120321

10-10

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,527-0000

NW NE SW, SEC. 11, T 20 S, R 29 W/EX

2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name McCoy Well # 1

Operator: Chief Drilling Company, Inc.

County Lane 154.31

Name & Address 224 East Douglas, Suite 350

Well Total Depth 4748 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5883

Address 151 North Main, Suite 700, Wichita, KS 67202

Company to plug at: Hour: 9 p.m. Day: 10 Month: 10 Year: 19 89

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Company (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2168-89'

1st plug at 2180' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 11:15 p.m. Day: 10 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,

2nd plug at 1400' with 80 sx cement,

3rd plug at 360' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-13-89

INV. NO. 26137

Signed Duane Rankin
(TECHNICIAN) RWR