

1031395

12-17

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,690-0000

NE SW NE, SEC. 25, T 20 S, R 29
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 31283

Lease Name Christian Church Well / 1

Operator: Rheem Resources, Inc.

County Lane 154.38

Name & Address 100 S. Main, Ste. 505

Well Total Depth 4750 feet

Address Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 8 p.m. Day: 17 Month: 12 Year: 1994

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2100' with 50 sx cement, 2nd plug at 1260' with 80 sx cement,

3rd plug at 840' with 40 sx cement, 4th plug at 290' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11 p.m. Day: 17 Month: 12 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,

2nd plug at 1260' with 80 sx cement,

3rd plug at 840' with 40 sx cement,

4th plug at 290' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# flowseal by Allied.

(Additional description is necessary, use BACK of this form.)

I (XXXX / did not) observe this plugging.

DATE 1-5-95

Signed Steve Durrant (TECHNICIAN)

INV. NO. 41971

12-17

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1994
12-21-94
CONSERVATION DIVISION
WICHITA, KANSAS