

To: 1 080170  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-101-21,754-0000  
SW SW SE, SEC. 6, T 20 S, R 28 W X  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 4197  
Operator: Dunne Oil Co.  
Name: 100 S. Main, Ste. 410  
Address: Wichita, KS 67202

Lease Name Heath Well / 1-6  
County Lane 152.75  
Well Total Depth 4700 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X  
Other well as hereinafter indicated  
Plugging Contractor Duke Drilling Co. License Number 5929  
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 12:30 p.m. Day: 16 Month: 1 Year: 19 98  
Plugging proposal received from Rich Wheeler  
(company name) Duke Drilling Co. (phone) 316-793-0834

to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2125-64'.  
1st plug at 2165' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,  
3rd plug at 650' with 40 sx cement, 4th plug at 300' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Scott Alberg  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None  
Operations Completed: Hour: 3:15 p.m. Day: 16 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 2165' with 50 sx cement,  
2nd plug at 1200' with 80 sx cement,  
3rd plug at 650' with 40 sx cement,  
4th plug at 300' with 40 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floeal by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED (X) I reserve this plugging.

DATE 1-23-98  
INV. NO. 49973  
1-16

Signed Kevin D. Smith  
(TECHNICIAN)