

To: 1090514
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-1-95
API NUMBER 15- 101-21,691-0000

NE SW SW, SEC. 30, T 20 S, R 28 W/E
990 feet from S section line
990 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31283
Operator: Rheem Resources, Inc.
Name & Address: 100 S. Main, Ste. 505
Wichita, KS 67202

Lease Name Smid Well # 1
County Lane
Well Total Depth 4750 154.38 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: 12 a.m. Day: 1 Month: 1 Year: 1995

Plugging proposal received from Tony Martin
(company name) Abercrombie (phone) 316-262-1841

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2126'
1st plug at 2130' with 50 sx cement, 2nd plug at 1180' with 80 sx cement,
3rd plug at 600' with 40 sx cement, 4th plug at 280' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 3:45 a.m. Day: 1 Month: 1 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement,
2nd plug at 1180' with 80 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 280' with 50 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
Date 1-25-95
Inv. No. 42096

Signed [Signature] (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED
1-5-95
JAN 5 1995