

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-21503-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 15-20S-27W  
1700 feet from S Section Line, 3260 feet from E Section Line  
Lease/Unit Name: THOMAS Well Number: 2  
County: LANE Total Vertical Depth: 4506 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: N HWY 283 PO BOX 544  
NESS CITY, KS 67560

Conductor Pipe: Size feet: \$ 146.45  
Surface Casing: Size 8.625 feet: 211  
Production: Size 4.5 feet: 4484 WITH 100 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/31/2002 11:20 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: MIKE J. FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: PUMP 60 SX CMT & 300# HULLS FOR BOTTOM PLUG. PUMP 11 SX GEL & 85 SX CMT. PRESSURE TEST. CHRCK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/31/2002 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:


PORT COLLAR AT 1912' WITH 325 SX CMT. CEMENTED TO SURFACE. OPEN HOLE. PUMP 60 SX CMT & 300# HULLS FOR BOTTOM PLUG. PUMP 11 SX GEL & 85 SX CMT. MAXIMUM PRESSURE 2000#. SHUT IN WITH 1500#. TIED ONTO BACKSIDE AND PRESSURED TO 500#. HELD.

1-9-03

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Michael Maier  
(TECHNICIAN)

INVOICED

DATE 1-10-03

INV. NO. 2003061054