

10-22

To: 1 061152
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,491-~~000~~
C NW NW, SEC. 21, T 20 S, R 27 W/E
4620 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 North Market, Suite 1000
Wichita, KS 67202

Lease Name Prose Well # 1
County Lane 151.39
Well Total Depth 4658 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 6033
Address 250 North Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 8 a.m. Day: 22 Month: 10 Year: 19 88

Plugging proposal received from Steve Carlton
(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2617' GL
Anhydrite 1933-75'
1st plug at 1975' with 50 sx cement. 2nd plug at 1235' with 80 sx cement,
3rd plug at 240' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-27-88
OCT 27 1988

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11 a.m. Day: 22 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1975' with 50 sx cement,
2nd plug at 1235' with 80 sx cement,
3rd plug at 240' with 50 sx cement,
4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 10-31-88
INV. NO. 22852

Signed Paul A. Luthi (TECHNICIAN)