

1 070904

1-9

20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,447-00-00

N/2 NE, SEC. 7, T 16 S, R 17 W/E

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Breit Well # 2

Operator: A F G Energy, Inc.

County Rush 114.07

Name & Address P.O.Box 605

Well Total Depth 3510 feet

Russell, KS 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1049

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 9 Month: 1 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 3509' w/275 sx cement, CIBP 3410', Perfs at 3084-3474' (9 sets)

1st plug sand back to 3030' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 9 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 2960' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement down 8 5/8".

Maximum pressure 900 psi and shut in 550 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (If desired, observe this plugging.)

DATE 2-8-91

Signed Dan Gooden (TECHNICIAN)

INV. NO. 30615