

1-13

1-120878

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API number: 165-21,060-00-00

C SW SW /4 SEC. 08, 16 S, 17 W
660 feet from S section line
4620 feet from E section line

Operator license# 3456 Lease Pfeifer "B" well # 1Operator: AFG Energy Inc. County Rush

Address: P.O. Box 458 Well total depth 3600 feet
Hays, KS 67601-0458 Conductor Pipe: 0 inch @ 0 feet
 Surface pipe 8 5/8 Inch @ 1126 feet

Aband. Oil well , Gas well X, Input well , SWD , D & A Plugging contractor: AFG Energy Inc. License# 3456Address: P.O. Box 458, Hays, KS 67601-0458Company to plug at: Hour: 11:30 am Day: 13 Month: January Year: 1994Plugging proposal received from: Terry PieskerCompany: AFG Energy Inc. Phone: 913-625-6374

Were: 4 1/2" at 3599' w/275 sx cement, Perfs at 2616-2720', PBTD 2730'
1st plug pump in 4 1/2" casing with 200 lbs. hulls and 130 sx cement,
2nd plug pump in 8 5/8" x 4 1/2" annulus with 200 sx cement.

Plugging Proposal Received by: Duane Rankin
 Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1 p.m., Day: 13, Month: January, Year: 1994

Actual plugging report: 1st plug pumped into 4 1/2" casing with 150 lbs. hulls and
130 sx cement. Pumping pressure 0-500 psi and shut in 500 psi.
2nd plug pumped into 8 5/8" x 4 1/2" annulus with 200 sx cement. Pumping pressure
0-600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered no casing.I did[X] / did not[] observe the plugging.Duane Rankin

(agent)

RECEIVED
 FORM AFE 2/77 CORPORATION COMMISSION

01-21-1994
 JAN 21 1994

INVOICED

DATE 1-24-94INV. NO. 39754

CONSERVATION DIVISION
 Wichita, Kansas