

6-1

1 070682

API NUMBER 15-165-21,032-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C W/2 SW SW, SEC. 11, T 16 S, R 17 W/E

660 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Hertal "A" Well # 1

Operator: American Warriors Inc.

County Rush 116.81

Name & Address P.O. Box 399

Well Total Depth 3594 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Paramount Casing Interprises License Number 3763

Address Box 861, Hays, KS 67601

Company to plug at: Hour: 2:15 p.m. Day: 1 Month: 6 Year: 19 89

Plugging proposal received from Ron Geist

(company name) Paramount Casing Interprises (phone) 913-628-1099

were: 5 1/2" at 3592' PBDT 3519' Perfs at 3473-79' DV tool at 1121'

1st plug sand back to 3420' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 150 sx cement, 20 sx gel, and 5 sx hulls.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 p.m. Day: 1 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3420' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Maximum pressure 900 psi and shut in 600 psi.

RECEIVED STATE CORPORATION COMMISSION

JUN - 8 1989 06-08-1989

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2323' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(copy to back) observe this plugging.

DATE 6-9-89

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 25041