

To: 1 071124 11-3  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-165-20,439-00-0026R

NE NW NE, SEC. 11, T 16 S, R 17 W/E

4950 feet from S section line

1650 feet from E section line

Lease Name Anna Stegman Well # 1

County Rush

Well Total Depth 3561 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1079

TECHNICIAN'S PLUGGING REPORT

Operator License # 30572

Operator: KLB Operating

Name: Drawer B

Address

Plainville, KS

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Paramount Ent. License Number 3763

Address P.O. Box 861, Hays, KS 67601

Company to plug at: Hour: 11 a.m. Day: 3 Month: 11 Year: 19 92

Plugging proposal received from Ron Geist

(company name) Paramount Ent. (phone) 913-628-1099

were: 5 1/2" at 3561' w/175 sx cement, PBD 3542', Perfs at 3239-3433'

1st plug sand back to 3189' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 200 lbs. hulls and 200 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 3 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3189' and dumped 5 sx cement on top of sand

through bailer,

2nd plug pumped 200 lbs. hulls and 200 sx cement down 8 5/8".

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. Recovered 2600' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Dan Goodrow (TECHNICIAN)